PD Modification Application: MM 25-0745

Zoning Hearing Master Date:

July 21, 2025

BOCC Land Use Meeting Date:

September 9, 2025



Development Services Department

1.0 APPLICATION SUMMARY

Applicant: Eisenhower Property Group, LLC

FLU Category: RES-4 (The Grove Parcel)

Service Area: Urban

Site Acreage: 358.3 - Overall PD

178.0 – The Grove Parcel

Community Balm, SouthShore Areawide

Plan Area: Systems

Overlay: None



Introduction Summary:

The subject site is zoned PD 18-0304, as most recently modified by PRS 23-0030. The zoning was originally approved in 2018 as a Planned Village development consisting of two non-contiguous areas, the "Rhodine Borrow Pit" and the "Grove Parcel." The "Rhodine Borrow Pit" permits 271 single-family homes, and the "Grove Parcel" permits 356 single-family homes.

The request seeks to amend the entitlements of the "Grove Parcel" by increasing the permitted number of single-family homes to 700 units and remove commercial entitlements. These changes come after recently adopted CPAs (CPA 24-46 and 24-47) which changed "The Grove Parcel" from the RP-2 to RES-4 Future Land Use Category and the service area from Rural to Urban. As a result, "Grove Parcel" is no longer to be developed as a Planned Village and seeks to remove conditions related to required commercial nodes and other developmental requirements.

Existing Approval(s):	Proposed Modification(s):
The Grove Parcel Entitlements:	The Grove Parcel Entitlements:
- Residential Single-Family: 356 units	- Residential Single-Family: 700 units
- Non-residential SF: 5,000 square feet	- Non-residential SF: 0 square feet
- Village Green SF: 4,806 square feet	- Village Green SF: 0 square feet
Develop as a Planned Village	No longer to be developed as a Planned Village
Minimum lot size: 4,400/5,500 square feet	Minimum lot size: 4,400 square feet
Minimum lot width: 40 feet/50 feet	Minimum lot width: 40 feet
300-foot wide buffer south of folio 77850.000	No buffer to be provided

Additional Information:			
PD Variation(s):	None Requested as part of this application		
Waiver(s) to the Land Development Code:	None Requested as part of this application		

APPLICATION NUMBER: MM 25-0745

ZHM HEARING DATE: July 21, 2025


BOCC LUM MEETING DATE: September 9, 2025 Case Reviewer: Jared Follin

Planning Commission Recommendation:	Development Services Recommendation:		
Consistent	Approvable, subject to proposed conditions		

Case Reviewer: Jared Follin

2.0 LAND USE MAP SET AND SUMMARY DATA

2.1 Vicinity Map




Context of Surrounding Area:

The subject property is located within the Urban Service Area and within the Balm Community area. The surrounding area primarily consists of agricultural and residential uses. Grove Parcel primarily fronts Balm Wimauma Road.

2.0 LAND USE MAP SET AND SUMMARY DATA

2.2 Future Land Use Map




Case Reviewer: Jared Follin

Subject Site Future Land Use Category:	Residential- 4 (RES-4)
Maximum Density/F.A.R.:	4.0 dwelling units per gross acre / 0.25 FAR
Typical Uses:	Agricultural, residential, neighborhood commercial, office uses, multi- purpose projects and mixed-use development.

2.0 LAND USE MAP SET AND SUMMARY DATA

2.3 Immediate Area Map



Case Reviewer: Jared Follin

Adjacent Zonings and Uses				
Location:	Zoning:	Maximum Density/F.A.R. Permitted by Zoning District: Allowable Use:		Existing Use:
North	AS-1	1 dwelling unit per acre	Agriculture/Single-Family Conventional	Residential
CN	CN	.20 FAR	Commercial Neighborhood	Undeveloped
South	PD 17-0619	3.5 dwelling units per acre / FAR 0.35	Single-Family Conventional / Limited Neighborhood Retail	Residential / Agriculture
East	AR	1 dwelling unit per 5 acres	Agriculture/Single-Family Conventional	Residential
EdSL	PD 17-0619	PD 17-0619	3.5 dwelling units per acre / FAR 0.35	Residential / Agriculture

APPLICATION NUMBER: MM 25-0745

ZHM HEARING DATE: July 21, 2025


BOCC LUM MEETING DATE: September 9, 2025 Case Reviewer: Jared Follin

	95-0076	4 dwelling units per acre / 0.05 FAR	Church and related uses, childcare center, agriculture uses, farmworker housing	Church
West	17-0619	PD 17-0619	3.5 dwelling units per acre / FAR 0.35	Residential / Agriculture
AS-0.4	AS-0.4	1 dwelling unit per 2.5 acres	Agriculture/Single-Family Conventional	Residential
	ASC-1	1 dwelling unit per acre	Agriculture/Single-Family Conventional	Residential

2.0 LAND USE MAP SET AND SUMMARY DATA

2.4 Approved Site Plan (partial provided below for size and orientation purposes. See Section 8.1 for full site plan)


Case Reviewer: Jared Follin



Case Reviewer: Jared Follin

2.0 LAND USE MAP SET AND SUMMARY DATA

2.5 Proposed Site Plan (partial provided below for size and orientation purposes. See Section 8.2 for full site plan)



APPLICATION NUMBER: MM 25-0745

ZHM HEARING DATE: July 21, 2025

BOCC LUM MEETING DATE: September 9, 2025 Case Reviewer: Jared Follin

3.0 TRANSPORTATION SUMMARY (FULL TRANSPORTATION REPORT IN SECTION 9 OF STAFF REPORT)

Adjoining Roadways (check if applicable)				
Road Name	Classification	Current Conditions	Select Future Improvements	
Balm Wimauma Rd.	County Collector — Urban/Rural	2 Lanes ☑ Substandard Road ☐ Sufficient ROW Width	□ Corridor Preservation Plan □ Site Access Improvements □ Substandard Road Improvements □ Other	
Shelley Ln.	County Local - Urban	2 Lanes ☑ Substandard Road ☐ Sufficient ROW Width	☐ Corridor Preservation Plan ☐ Site Access Improvements ☑ Substandard Road Improvements ☐ Other	
Balm Rd.	County Collector - Rural	2 Lanes ☑ Substandard Road ☐ Sufficient ROW Width	☐ Corridor Preservation Plan ☐ Site Access Improvements ☐ Substandard Road Improvements ☐ Other	

Project Trip Generation ☐ Not applicable for this request					
Average Annual Daily Trips A.M. Peak Hour Trips P.M. Peak Hour Trips					
Existing	4,080	308	442		
Proposed	6,045	438	619		
Difference (+/-)	(+)1,965	(+)130	(+)177		

^{*}Trips reported are based on gross external trips unless otherwise noted.

Connectivity and Cross Access ☐ Not applicable for this request					
Project Boundary	Primary Access	Additional Connectivity/Access	Cross Access	Finding	
North	X	Choose an item.	Choose an item.	Choose an item.	
South		Choose an item.	Choose an item.	Choose an item.	
East	X	Choose an item.	Choose an item.	Choose an item.	
West	X	Choose an item.	Choose an item.	Choose an item.	
Notes:					

Design Exception/Administrative Variance □ Not applicable for this request				
Road Name/Nature of Request Type Finding				
Balm Wimauma Rd/Substandard Road	Design Exception Requested	Approvable		
	Choose an item.	Choose an item.		
	Choose an item.	Choose an item.		
	Choose an item.	Choose an item.		
Notes:				

APPLICATION NUMBER:	MM 25-0745	
ZHM HEARING DATE:	July 21, 2025	
BOCC LUM MEETING DATE:	September 9, 2025	Case Reviewer: Jared Follin

4.0 ADDITIONAL SITE INFORMATION & AGENCY COMMENTS SUMMARY

INFORMATION/REVIEWING AGENCY				
Environmental:	Comments Received	Objections	Conditions Requested	Additional Information/Comments
Environmental Protection Commission	⊠ Yes □ No	☐ Yes ☑ No	⊠ Yes □ No	Wetlands Present
Natural Resources		☐ Yes ⊠ No	⊠ Yes □ No	
Conservation & Environ. Lands Mgmt.	⊠ Yes □ No	☐ Yes ⊠ No	☐ Yes ⊠ No	
Check if Applicable:		Vater Wellfield Pro	tection Area	
☐ Wetlands/Other Surface Waters	☐ Significan	t Wildlife Habitat		
☐ Use of Environmentally Sensitive Land	☐ Coastal H	igh Hazard Area		
Credit	☐ Urban/Sul	burban/Rural Scen	ic Corridor	
☐ Wellhead Protection Area	☐ Adjacent	to ELAPP property		
☐ Surface Water Resource Protection Area	☐ Other			
Public Facilities:	Comments Received	Objections	Conditions Requested	Additional Information/Comments
Transportation ☑ Design Exc./Adm. Variance Requested ☑ Off-site Improvements Provided	⊠ Yes □ No	☐ Yes ⊠ No	⊠ Yes □ No	
Service Area/ Water & Wastewater ⊠Urban □ City of Tampa □Rural □ City of Temple Terrace	⊠ Yes □ No	☐ Yes ⊠ No	□ Yes ⊠ No	
Hillsborough County School Board Adequate □ K-5 □6-8 □9-12 □ N/A Inadequate □ K-5 □6-8 □9-12 □ N/A	□ Yes ⊠ No	☐ Yes ☐ No	☐ Yes ☐ No	
Impact/Mobility Fees Single-Family Detached (Fee estimate is base Mobility: \$13,038 * 344 = \$4,485,072 Parks: \$2,145 * 344 = \$737,880 School: \$8,227 * 344 = \$2,830,088 Fire: \$335 * 344 = \$115,240 Total per House: \$23,745 * 344 = \$8,168,280		.f.)		
Comprehensive Plan:	Comments Received	Findings	Conditions Requested	Additional Information/Comments

Comprehensive Plan:	Received	Findings	Requested	Information/Comments

APPLICATION NUMBER:	MM 25-0745				
ZHM HEARING DATE: BOCC LUM MEETING DATE:	July 21, 2025 September 9, 2025		Case Re	eviewer: Jared Fol	llin
Planning Commission					
☐ Meets Locational Crit	eria ⊠N/A	⊠ Yes	☐ Inconsistent	□ Yes	
☐ Locational Criteria Wa	aiver Requested	□No	⊠ Consistent	⊠ No	
☐ Minimum Density Me	et ⊠ N/A				

5.0 IMPLEMENTATION RECOMMENDATIONS

5.1 Compatibility

Applicant seeks to make modifications to the "Grove Parcel" by increasing the number of permitted single-family conventional units, amend lot development standards and remove commercial entitlements.

Property recently went through a Comprehensive Plan Amendment, changing the Future Land Use Category from RP-2 (Residential Planned-2) to RES-4 (Residential-4). Existing PD proposed residential development following the RP-2 requirements, including providing commercial nodes, allowing neighborhood retail uses, throughout the development. These standards are no longer applicable and are not implemented in this zoning.

While the "Rhodine Parcel" is included in this rezoning, no changes to the existing requirements are proposed and conditions pertaining to this area are to remain.

Development Services does not foresee any compatibility concerns with the proposed Planned Development. Residential is appropriate for the area and will not pose any negative impacts to the area.

5.2 Recommendation

Based on the above considerations, staff finds the proposed Major Modification, subject to the conditions, approvable.

APPLICATION NUMBER: MM 25-0745
ZHM HEARING DATE: July 21, 2025

BOCC LUM MEETING DATE: September 9, 2025 Case Reviewer: Jared Follin

Requirements for Certification:

1. Site plan to delineate 50-foot wide buffer in areas previously approved – the Grove Parcel.

6.0 PROPOSED CONDITIONS

Approval - Approval of the request, subject to the conditions listed below, is based on the general site plan submitted June 30^{th} , 2025.

1. The Rhodine Borrow Pit parcel shall be permitted a maximum of 271 single-family lots within a maximum residential development area of 77.17 acres and developed in accordance with the following development standards. The maximum number of units permitted in the Rhodine Borrow Pit parcel is identified as Critical Design Feature. Any change to this number will require a Major Modification to be reviewed in accordance with the procedures established in LDC Part 10.03.00.

Minimum lot size: 4,400 square feet/5,500 square feet

Minimum lot width: 40 feet/50 feet
Minimum front yard setback: 20 feet
10 feet for front yards functioning as side yards*

Minimum side yard setback: 5 feet
Minimum rear yard setback: 15 feet

Maximum building height: 35 feet/2-stories

- 1.1 The project's residential development area shall consist of a maximum of 77.17 acres. Correspondingly, the remaining 99.9 acres shall be utilized as open space in accordance with Comprehensive Plan Policy 14.2. A total of 0.23 acres shall be dedicated to the Village Node to provide a maximum FAR of 0.35 for the required on-site retail square footage. The Village Node acreage shall not be considered open space or residential development area.
- 1.2 Along the southern PD boundary of the Rhodine Borrow Pit area, adjacent to PD 98-0812 (Triple Creek), single-family residential lots/units shall be permitted to be partially located in both the subject PD and PD 98-0812 as part of a unified plan of development. At the time of platting, these lots shall be assigned to either the subject PD or PD 98-0812 and in no case shall the maximum number of permitted units in either PD be exceeded. These lots shall follow the development standards and any additional supplement requirements of the PD they are assigned to for accounting purposes. Vehicular and pedestrian cross access between the common boundary line shall be permitted.
- 2. For lots at a width of less than 50 feet, the following shall apply:
 - 2.1 Garages shall be setback a minimum of 25 feet. Garages accessed from a front yard functioning as a side yard shall be setback a minimum of 20 feet.
 - 2.2 A 2-car garage and a minimum 18 foot wide driveway shall be provided for each unit.

^{*}Garages accessed from front yards functioning as side yards shall be setback a minimum of 20 feet.

APPLICATION NUMBER:	MM 25-0745
ZHM HEARING DATE:	July 21, 2025
BOCC LLIM MEETING DATE:	Santambar 9 2025

2.3 All driveways shall be provided in an alternating pattern on the left or right side of the unit's front façade. Homes shall not have the same driveway location (left or right side) as the adjacent home. The alternating pattern may be adjusted at corner lots as necessary.

Case Reviewer: Jared Follin

- 2.4 A variety of garage door designs shall be provided and there shall be no two identical garage door designs adjacent to each other.
- 2.5 Each unit's primary entrance door shall face the roadway.
- 2.6 Street trees may include an alternating pattern of shade and ornamental trees, subject to final design and approval by Natural Resources staff.
- 3. A maximum of 3,658.5 square feet of neighborhood retail uses shall be provided within Commercial Pocket A (Rhodine Borrow Pit Village Node). Neighborhood retail uses shall include grocery stores, food/produce markets, convenience stores, pharmacies and other retail uses permitted in the CN zoning district.
- 4. The Rhodine Borrow Pit Village Node shall meet the following:
 - 4.1 The Village Node may also contain office uses, residential support uses (such as churches, adult care centers and daycare centers) and government uses (such as schools, government offices/services). Square footage for these uses shall not count towards the minimum square footage required for onsite neighborhood retail. The maximum F.A.R. permitted within the entire Village Node is 0.35.
 - 4.2 No minimum building setbacks shall be required.
 - 4.3 Building height shall be limited to a maximum of 35 feet with no additional setback for buildings over 20 feet in height required.
 - 4.4 Buffering and screening in accordance with Land Development Code Section 6.06.06 shall be provided along adjacent properties of differing land use classifications.
 - 4.5 Parking lots in the Village Node shall be located at the rear or to the side of buildings, or to the interior of a block. Not more than two rows of angled parking shall be located between a building and the roadway.
 - 4.6 Signage within the Village Node shall be limited to monument signs.
- 5. Prior to the issuance of building permits for more than 75% of the residential units (lots 203-271), Certificates of Occupancy shall be issued for a minimum of 50 percent of the 3,658.5 s.f. of required on-site neighborhood retail in the Village Node. Prior to the building permits for more than 95% of the residential units (lots 257-271), Certificates of Occupancy shall be issued for the remaining 3,658.5 square feet of neighborhood retail in the Village Node.

APPLICATION NUMBER:	MM 25-0745
ZHM HEARING DATE:	July 21, 2025
DOCC LLIM MEETING DATE:	Sontombor 0 20

BOCC LUM MEETING DATE: September 9, 2025 Case Reviewer: Jared Follin

6. The developer shall provide a pedestrian system of sidewalks and/or stabilized pathways (a minimum of 5 feet in width) throughout the project with direct connections between the residential, open space and Village Node areas.

- 7. A 50-foot wide buffer shall be provided where depicted on the general site plan. This buffer is to be platted as a separate tract to be owned and maintained by the Homeowner's Association, or other similar entity. Within the buffer, screening shall be provided and shall be either 1) screening to consist of two or more of the following for an overall height of six feet: a berm (4:1 slope), a continuous row of evergreen shrubs at a minimum height of 24" and/or a solid wooden fence, PVC fence or wall architecturally finished on both sides; or 2) a six foot high wooden fence, PVC fence or wall architecturally finished on both sides and a row of evergreen shade trees at a minimum of 10 feet in height and minimum 2" caliper at the time of planting planted on 20 foot centers. Should the buffer abut a right-or-way, use of a six foot high wooden fence shall not be used. Additionally, should the buffer abut a right-of-way, hedges or trees shall not be blocked by a fence/wall from the view of the roadway and properties facing the village.
- 8. The parcel identified by Folio Number 77420.5000 is adjacent to the Triple Creek Preserve. Per LDC Section 4.01.00, compatibility of the development with the preserve will be ensured with a compatibility plan that addresses issues related to the development such as, but not necessarily limited to, access, prescribed fire, and landscaping. The compatibility plan shall be proposed by the developer, reviewed and approved by the Conservation and Environmental Lands Management Department, and shall be required as a condition of granting a Natural Resources Permit.
- 9. As Rhodine Road is a substandard collector roadway, the developer shall improve Rhodine Road between the project driveway and the nearest standard roadway to current County standards unless otherwise approved in accordance with Section 6.04.02.B of the Hillsborough County Land Development Code (LDC). Deviations from Transportation Technical Manual (TTM) standards may be considered in accordance with Section 1.7.2 and other applicable sections of the Hillsborough County TTM.
- 10. Utilization of proposed access points along the project's southern boundary shall require modification of the adjacent Planned Development (to permit such cross access).
- 11. The developer shall construct the following site access improvements, unless otherwise approved by Hillsborough County Public Works:
 - a. An eastbound to southbound right turn lane on Rhodine Road into the project; and,
 - A westbound to southbound left turn lane on Rhodine Road into the project. Such improvements may require the developer to dedicate or otherwise acquire additional right-ofway.
- 12. The developer shall construct an internal project roadway beginning at Rhodine Road and continuing for a distance of approximately 3,650 ft (i.e. to the south most point of the area of modification shown on the PD site plan for PRS 23-0030, hereafter referred to as the "Rhodine Road Connector"). The Rhodine Road Connector shall be constructed in two segments: (1) first, the southernmost +/- 1,850 ft

(i.e., between the southmost point of the Rhodine Road Connector and the existing entrance into Folio 77420.6000 (the "South Segment"); and, (2) second, from the existing entrance into Folio 77420.6000 to Rhodine Road (the "North Segment").

Case Reviewer: Jared Follin

- Building permit applications for more than 75% of the residential units (i.e. for the 204th-270th residential unit) may not be filed by the developer until the developer has:
 - a. Substantially completed the South Segment of the Rhodine Road Connector and such facility is open to traffic; and,
 - b. Posted (and the County has accepted) a performance bond which guarantees construction of the North Segment. Such performance bond shall be issued in an amount equal to 125% of the estimated cost to construct the facility.
- 12.2 Building permits for more than 75% of the residential units (i.e.for the 204th-270th residential unit) may not be issued by the County until the developer has substantially completed the North Segment of the Rhodine Road Connector and such facility is open to traffic.
- 12.3 The first 1,800 feet of the Rhodine Road Connector (south of Rhodine Road) shall be utilized as a Shared Access Facility. The purpose of this shared access facility is to serve:
 - a. Future development on folio 77409.3000, consistent with the adjacent PD 05-0110; and,
 - b. Existing/future development on folio 77420.6000.

Notwithstanding anything shown on the PD site plan to the contrary, vehicular and pedestrian access may be taken anywhere along the project boundaries with folios 77409.3000 and 77420.6000, subject to the review and approval of Hillsborough County Public Works.

13. In accordance with the Hillsborough County Corridor Preservation Plan, the developer shall preserve up to 5 feet of right-of-way along its Rhodine Road frontage, such that a minimum of 55 feet of right-of-way is preserved south of the existing right-of-way centerline. Only those interim uses allowed by the Hillsborough County LDC shall be permitted within the preserved right-of-way. The right-of-way preservation area shall be shown on all future site plans, and building setbacks shall be calculated from the future right-of-way line.

The following shall apply to the Grove parcel:

14. The Grove parcel shall be permitted a maximum of 356 700 single-family lots and developed in accordance with the following development standards. The maximum number of units permitted in the Grove parcel is identified as Critical Design Feature. Any change to this number will require a Major Modification to be reviewed in accordance with the procedures established in LDC Part 10.03.00.

Minimum lot size: 4,400 square feet / 5,500 square feet

Minimum lot width: 40 feet / 50 feet

APPLICATION NUMBER:	MM 25-0745	
ZHM HEARING DATE:	July 21, 2025	
BOCC LUM MEETING DATE:	September 9, 2025	Case Reviewer: Jared Follin

Minimum front yard setback: 20 feet

10 feet for front yards functioning as side yards*

Minimum side yard setback:** 5 feet
Minimum rear yard setback:** 15 feet

Maximum building height: 35 feet/2-stories

- 14.1 Land Excavation shall be a permitted use on the Grove Parcel subject to approval of a Special Use Permit per Land Development Code Section 6.11.54. The maximum export permitted shall be 759,000 cubic yards from Pond N, 78,000 cubic yards from Pond SW and 238,000 cubic yards from Pond SE (as depicted in SU 19-1026) for a total of 1,075,000 cubic yards.
 - Special Use Permit 19-1026 shall expire three years from the date of Operating Permit approval. If an Operating Permit has not been issued for any portion of the land excavation within two years of the date of approval for PD modification 21-0033, as required in condition 2 of Special Use Permit 19-1026, then Special Use Permit 19-1026 shall expire.
- 15. For lots at a width of less than 50 feet, the following shall apply:
 - 15.1 Garages shall be setback a minimum of 25 feet. Garages accessed from a front yard functioning as a side yard shall be setback a minimum of 20 feet.
 - 15.21 A 2-car garage and a minimum 1816 foot wide driveway shall be provided for each unit.
 - 15.3 All driveways shall be provided in an alternating pattern on the left or right side of the unit's front façade. Homes shall not have the same driveway location (left or right side) as the adjacent home. The alternating pattern may be adjusted at corner lots as necessary.
 - 15.4 A variety of garage door designs shall be provided and there shall be no two identical garage door designs adjacent to each other.
 - 15.<u>52</u> Each unit's primary entrance door shall face the roadway.
 - 15.6 Street trees may include an alternating pattern of shade and ornamental trees, subject to final design and approval by Natural Resources staff.
- 16. This PD approves a waiver to the provision of 4,806 s.f. of on site neighborhood retail. A total of 5,038 square feet is provided off-site on folios 77886.0000 (a 3,238 square foot convenience store) and 77857.0000 (a 1,800 square foot post office).

^{*}when no access is taken from the front yard functioning as the side yard, the setback shall be a minimum of 10 feet. When access is taken from the front yard functioning as the side yard, the setback shall be a minimum of 20 feet. accessed from front yards functioning as side yards shall be setback a minimum of 20 feet.

^{**}Side yard setback should be 20 feet when used for access

^{***}Minimum rear setback of 5 feet for accessory structures and 3 feet for pool enclosures

Case Reviewer: Jared Follin

- 16.1 The 5,038 square feet on folios 77886.0000 and 77857.0000 shall not be used for any future onsite commercial waiver requests for other proposed Planned Villages.
- 17. The Grove Village Node (amenity/specialty retail depicted area) shall meet the following:
 - 17.1 The Village Node may contain a maximum of 5,000 square feet of neighborhood retail uses, office uses, residential support uses (such as churches, adult care centers and daycare centers) and government uses (such as schools, government offices/services). A maximum of 497 square feet of this 5,000 square feet may be developed with neighborhood retail uses permitted in the CN zoning district. The maximum F.A.R. permitted within the entire Village Node is 0.35.
 - 17.2 The Village Node may also contain neighborhood amenity uses, such as a pool, amenity area and clubhouse which shall not count towards the maximum F.A.R. permitted in the Village Node.
 - 17.2 No minimum building setbacks shall be required.
 - 17.3 Building height shall be limited to a maximum of 35 feet with no additional setback for buildings over 20 feet in height required.
 - 17.4 Buffering and screening in accordance with Land Development Code Section 6.06.06 shall be provided along adjacent properties of differing land use classifications.
 - 17.5 Parking lots in the Village Node shall be located at the rear or to the side of buildings, or to the interior of a block. Not more than two rows of angled parking shall be located between a building and the roadway.
 - 17.6 Signage within the Village Node shall be limited to monument signs.
- 18. A Village Square/Green (minimum size of 4,806 square feet) shall be provided where depicted on the general site plan. The Village Square/Green shall be bound on all sides by streets and improved with landscaping, walkways, benches, fountains, gazebos and/or similar amenities to encourage and accommodate use by village residents.
- 19. The developer shall provide a pedestrian system of sidewalks and/or stabilized pathways (a minimum of 5 feet in width) throughout the project with direct connections between the residential, open space, Village Square/Green and Village Node areas.
- 20.16. A 50-foot wide buffer shall be provided where depicted on the general site plan. Should the buffer be adjacent to a roadway requiring right-of-way preservation, the buffer shall be measured from the future right-of-way line. This buffer is to be platted as a separate tract to be owned and maintained by the Homeowner's Association, or other similar entity. Within the buffer, screening shall be provided and shall be either: 1) screening to consist of two or more of the following for an overall height of six feet: a berm (4:1 slope), a continuous row of evergreen shrubs at a minimum height of 24" and/or a

APPLICATION NUMBER:	MM 25-074

ZHM HEARING DATE: July 21, 2025

BOCC LUM MEETING DATE: September 9, 2025 Case Reviewer: Jared Follin

solid wooden fence, PVC fence or wall architecturally finished on both sides; or 2) a six foot high wooden fence, PVC fence or wall architecturally finished on both sides and a row of evergreen shade trees at a minimum of 10 feet in height and minimum 2" caliper at the time of planting planted on 20 foot centers. Should the buffer abut a right-or-way, use of a six foot high wooden fence shall not be used. Additionally, should the buffer abut a right-of-way, hedges or trees shall not be blocked by a fence/wall from the view of the roadway and properties facing the village. Any buffers abutting a right-of-way shall be measured from the roadway's preservation line.

20.16.a Should any portion of Balm-Wimauma Road be vacated (Option 1 and Option 2 in condition 17.d), the 50-foot wide buffer and screening shall not be required.

- 21.17. A 250-foot wide buffer shall be provided adjacent to folio 77850.0000, as depicted on the general site plan.
- <u>22.18.</u> The developer shall construct the following site access improvements, of which 18.a, 18.b or 18.c shall be constructed only if warranted per Section 6.04.04.D. of the Hillsborough County Land Development Code or unless otherwise approved in accordance the Section 6.04.02.B. administrative variance process:
 - 22.18.a An eastbound to southbound right turn lane on CR 672 at Shelley Ln.;

[COMPLETED]

22.18.b A westbound to southbound left turn lane on CR 672 at Shelley Ln.;

[COMPLETED]

2218.d.

- 22.18.c. A southbound to eastbound left turn lane and a northbound to eastbound right turn
 - <u>lane on Balm Wimauma Rd.</u> into the project's southernmost entrance; and, A southbound to eastbound left turn lane and a northbound and eastbound right turn

lane on Balm Wimauma Rd. into the project's New Jade entrance; and

One (1) of the following options (as depicted on the on the PD site plan) relating to site access and roadway reconfigurations proposed by the developer:

i. Option 1 – The developer shall construct an extension of Balm Wimauma Rd. (between its intersection with Balm Rd. and CR 672) as a 2-lane collector roadway. Within 6 months of acceptance of the roadway extension, the developer shall remove up to a +/- 1,300-foot long segment of existing Balm Wimauma Rd. south of CR 672. Specific limits of the segment to be removed shall be determined and approved by Hillsborough County Public Works. Utilization of this option is contingent upon the developer's ability to, at its sole cost, design the facility, obtain all required permits for construction, and acquire any additional right-of-way necessary for the proposed extension and related improvements. Utilization of this option is also contingent upon review and approval of the proposed roadway by Hillsborough County Public Works, including any turn lanes that may be required by the County at the intersection of the roadway extension with CR 672. In no event shall removal of the roadway section occur until such time as a cul-de-sac or other end of roadway treatment

July 21, 2025 September 9, 2025

acceptable to Hillsborough County Public Works is constructed and open to public traffic; or,

Case Reviewer: Jared Follin

Option 2 - The developer shall realign up to +/- 1,300 feet of Balm Wimauma Rd. (i.e. 18.e.ii. that portion immediately south of CR 672) such that it connects to Shelley Ln. Concurrent with the opening of the realigned roadway extension, the developer shall close the old/realigned roadway and, within 6 months, complete removal of the old/unutilized roadway. Specific limits of the segment to be realigned/removed shall be determined and approved by Hillsborough County Public Works. Utilization of this option is contingent upon the developer's ability to, at its sole cost, design the facility, obtain all required permits for construction, and acquire any additional right-of-way necessary for the proposed extension and related improvements. Utilization of this option is also contingent upon review and approval of the proposed roadway by Hillsborough County Public Works, including any turn lanes that may be required by the County at the newly created intersection of Balm Wimauma Rd. and Shelley Ln. The applicant shall also be responsible for preserving sufficient right-of-way necessary to accommodate a 2-lane enhanced roadway segment between the new intersection and CR 672; or,

- iii. Option 3 The developer shall construct a roundabout at the intersection of CR 672, Balm Wimauma Rd., Shelley Ln., and Balm Boyette Rd. This option may require the developer to dedicate or otherwise acquire additional right-of-way necessary to accommodate the roundabout. Notwithstanding anything herein to the contrary, utilization of this option shall relieve the developer of its obligation to construct the improvements listed in 1.a. and 1.b., above. Utilization of this option is also contingent upon review and approval of the proposed roundabout by Hillsborough County Public Works.
- 23.19. As Shelley Ln. is a substandard local roadway the developer will be required to improve Shelley Ln., between its southernmost access connection and CR 672 the intersection with Balm Wimauma Rd, to current County standards unless otherwise approved in accordance with Section 6.04.02.B. of the Hillsborough County LDC. Deviations from TTM standards may be considered in accordance with Section 1.7.2. and other applicable sections of the Hillsborough County TTM.
- 24.20. As Balm Wimauma Rd. may be a substandard collector roadway, the developer will be required to coordinate with Hillsborough County Public Works to determine the improvements that may be required prior to or concurrent with plat/site/construction plan approval. If MM 25-0745 is approved, the County Engineer will approve the Design Exception (dated July 9, 2025), which was found approvable on July 11, 2025, for Balm Wimauma Rd. substandard road improvements. As Balm Wimauma Rd. is a substandard rural collector roadway, the developer will be required to construct improvements that include 11-foot-wide lanes, 8-foot shoulders with 7 feet paved consistent with the Design Exception.
- 25. In accordance with the Hillsborough County Corridor Preservation Plan, the developer shall preserve up to 23 feet of right-of-way along its Balm Wimauma Rd. frontages, such that a minimum of 54 feet of right-of-way is preserved east and south of the existing right-of-way centerline. Only those interim uses

allowed by the Hillsborough County LDC shall be permitted within the preserved right-of-way. The right-of-way preservation area shall be shown on all future site plans, and building setbacks shall be calculated from the future right-of-way line.

Case Reviewer: Jared Follin

- 26.. In accordance with the Hillsborough County Corridor Preservation Plan, the developer shall preserve up to 14 feet of right of way along its CR 672 frontage, such that a minimum of 54 feet of right of way is preserved south of the existing right of way centerline. Only those interim uses allowed by the Hillsborough County LDC shall be permitted within the preserved right of way. The right of way preservation area shall be shown on all future site plans, and building setbacks shall be calculated from the future right of way line.
- 27. Notwithstanding anything shown on the PD site plan to the contrary, the relocation of the southernmost access on Balm Wimauma Rd. such that it is located a minimum of 330 feet from the nearest adjacent access connection, shall be made. However, the access point shall not be located any further than 600 feet from the southern boundary of folio 77850.0000. Alternatively, the developer shall obtain a Section 6.04.02.B. administrative variance from the Section 6.04.07 access spacing requirements.

The following shall apply to both Planned Villages parcels:

- 28.21. Access shall be provided as shown on the PD site plan unless otherwise provided herein these conditions. Internal roadways may be public or private, and if private, and if private, roadways may be gated (except for those portions functioning as shared access roadways, as required herein these conditions).
- 29.22. Notwithstanding anything on the PD site plan or herein these conditions to the contrary, bicycle and pedestrian access may be permitted anywhere along the project boundaries.
- 30.23. Approval of this zoning petition by Hillsborough County does not constitute a guarantee that the Environmental Protection Commission of Hillsborough County (EPC) approvals/permits necessary for the development as proposed will be issued, does not itself serve to justify any impact to wetlands, and does not grant any implied or vested right to environmental approvals.
- 31.24. The construction and location of any proposed wetland impacts are not approved by this correspondence, but shall be reviewed by EPC staff under separate application pursuant to the EPC Wetlands rule detailed in Chapter 1-11, Rules of the EPC, (Chapter 1-11) to determine whether such impacts are necessary to accomplish reasonable use of the subject property.
- Prior to the issuance of any building or land alteration permits or other development, the approved wetland/other surface water (OSW) line must be incorporated into the site plan. The wetland/OSW line must appear on all site plans, labeled as "EPC Wetland Line", and the wetland must be labeled as "Wetland Conservation Area" pursuant to the Hillsborough County Land Development Code (LDC).

APPLICATION NUMBER:	MM 25-0745
ZHM HEARING DATE:	July 21, 2025

BOCC LUM MEETING DATE: September 9, 2025 Case Reviewer: Jared Follin

- <u>3326.</u> Final design of buildings, stormwater retention areas, and ingress/egresses are subject to change pending formal agency jurisdictional determinations of wetland and other surface water boundaries and approval by the appropriate regulatory agencies.
- 27. Wetlands or other surface waters are considered Environmentally Sensitive Areas and are subject to Conservation Area and Preservation Area setbacks. A minimum setback must be maintained around these areas which shall be designated on all future plan submittals. Only items explicitly stated in the condition of approval or items allowed per the LDC may be placed within the wetland setback. Proposed land alterations are restricted within the wetland setback areas.
- 28. Approval of this petition by Hillsborough County does not constitute a guarantee that Natural Resources approvals/permits necessary for the development as proposed will be issued, does not itself serve to justify any impacts to trees, natural plant communities or wildlife habitat, and does not grant any implied or vested right to environmental approvals.
- 29. The construction and location of any proposed environmental impacts are not approved by this correspondence, but shall be reviewed by Natural Resources staff through the site and subdivision development plan process pursuant to the Land Development Code.
- 32. Prior to the issuance of any building or land alteration permits or other development, the approved wetland/other surface water (OSW) line must be incorporated into the site plan. The wetland/ OSW line must appear on all site plans, labeled as "EPC Wetland Line", and the wetland must be labeled as "Wetland Conservation Area" pursuant to the Hillsborough County Land Development Code (LDC).
- 33. Final design of buildings, stormwater retention areas, and ingress/egresses are subject to change pending formal agency jurisdictional determinations of wetland and other surface water boundaries and approval by the appropriate regulatory agencies.
- 3430. If the notes and/or graphic on the site plan are in conflict with specific zoning conditions and/or the Land Development Code (LDC) regulations, the more restrictive regulation shall apply, unless specifically conditioned otherwise. References to development standards of the LDC in any stated conditions shall be interpreted as the regulations in effect at the time of preliminary site plan/plat approval.
- 3531. In accordance with LDC Section 5.03.07.C, the certified PD general site plan shall expire for the internal transportation network and external access points, as well as for any conditions related to the internal transportation network and external access points, if site construction plans, or equivalent thereof, have not been approved for all or part of the subject Planned Development within 5 years of the effective date of the PD unless an extension is granted as provided in the LDC. Upon expiration, recertification of the PD General Site Plan shall be required in accordance with provisions set forth in LDC Section 5.03.07.C.

	July 21, 2025 September 9, 2025	Case Reviewer: Jared Follin
Zoning Administrator Sig	gn Off:	J. Brian Grady

SITE, SUBDIVISION AND BUILDING CONSTRUCTION IN ACCORDANCE WITH HILLSBOROUGH COUNTY SITE DEVELOPMENT PLAN & BUILDING REVIEW AND APPROVAL.

Approval of this re-zoning petition by Hillsborough County does not constitute a guarantee that the project will receive approvals/permits necessary for site development as proposed will be issued, nor does it imply that other required permits needed for site development or building construction are being waived or otherwise approved. The project will be required to comply with the Site Development Plan Review approval process in addition to obtain all necessary building permits for on-site structures.

7.0 ADDITIONAL INFORMATION AND/OR GRAPHICS

APPLICATION NUMBER:

MM 25-0745


APPLICATION NUMBER: MM 25-0745

ZHM HEARING DATE: July 21, 2025 BOCC LUM MEETING DATE: September 9, 2025

Case Reviewer: Jared Follin

8.0 SITE PLANS (FULL)

8.1 Approved Site Plan (Page 1 of 4)




APPLICATION NUMBER:	MM 25-074
---------------------	-----------

Case Reviewer: Jared Follin

8.0 SITE PLANS (FULL)

8.1 Approved Site Plan (Page 2 of 4)




APPLICATION NUMBER:	MM 25-0745

ZHM HEARING DATE: July 21, 2025

BOCC LUM MEETING DATE: September 9, 2025 Case Reviewer: Jared Follin

8.0 SITE PLANS (FULL)

8.1 Approved Site Plan (Page 3 of 4)




APPLICATION NUMBER: MM 25-0745
ZHM HEARING DATE: July 21, 2025

BOCC LUM MEETING DATE: September 9, 2025 Case Reviewer: Jared Follin

8.0 SITE PLANS (FULL)

8.1 Approved Site Plan (Page 4 of 4)




APPLICATION NUMBER: MM 25-0745
ZHM HEARING DATE: July 21, 2025

BOCC LUM MEETING DATE: September 9, 2025 Case Reviewer: Jared Follin

8.0 SITE PLANS (FULL)

8.2 Proposed Site Plan (Page 1 of 6)




APPLICATION NUMBER:	MM 25-074
---------------------	-----------

Case Reviewer: Jared Follin

8.0 SITE PLANS (FULL)

8.2 Proposed Site Plan (Page 2 of 6)




APPLICATION NUMBER:	MM 25-0745
ZHM HEARING DATE:	July 21, 2025

ZHM HEARING DATE: July 21, 2025

BOCC LUM MEETING DATE: September 9, 2025 Case Reviewer: Jared Follin

8.0 SITE PLANS (FULL)

8.2 Proposed Site Plan (Page 3 of 6)




APPLICATION NUMBER: MM 25-0745
ZHM HEARING DATE: July 21, 2025

BOCC LUM MEETING DATE: September 9, 2025 Case Reviewer: Jared Follin

8.0 SITE PLANS (FULL)

8.2 Proposed Site Plan (Page 4 of 6)




APPLICATION NUMBER: MM 25-0745
ZHM HEARING DATE: July 21, 2025

BOCC LUM MEETING DATE: September 9, 2025 Case Reviewer: Jared Follin

8.0 SITE PLANS (FULL)

8.2 Proposed Site Plan (Page 5 of 6)



APPLICATION NUMBER: ZHM HEARING DATE:	MM 25-0745 July 21, 2025	
BOCC LUM MEETING DATE:	September 9, 2025	Case Reviewer: Jared Follin
8.0 SITE PLANS (FULL)		
8.2 Proposed Site Plan	(Page 6 of 6)	
RHODINE PARCEL FOLIOS 1	NE GROVE PARCE FOLIOS MM Amonted Pured — A parties of 0778400708	Sentagenet Sony, 100 100 100 100 100 100 100 100 100 10
0774206512 0774206632 0774206746 0774206800 0774206974 0774206514 0774206534 0774206748 0774206802 0774206976 0774205516 0774206836 0774206730 0774206804 0774206976 0774205516 0774206838 0774206732 0774206806 0774206980	0778480012 0778480126 0778480240 0778480354 0778480468 0778480562 0778480687 0778480180 0778880180 0778880180	to natives.
0774206520 0774206840 0774206734 0774206888 0774206892 0774206522 077420642 0774206730 0774206730 0774206894 0774206524 0774206844 0774206738 0774206730 0774206988 0774205280 0774208846 0774206730 0774206731 0774206988 0774205280 0774208846 0774206730 0774206731 0774206888	9778460022 0778460134 0778460245 0778480262 0778460276 077848050 077848050 9778450022 0778460136 0778480250 0778460364 0778460476 0778480502 0778480504 9778460024 0778460136 0778460252 0778480366 0778480480 0778480504 97778460024 0778460136 0778460254 0778480366 0778460480 0778480584 97778460032 0778460140 0778460254 0778480368 0778460482 0778480586	ONEMARA
077420630 0774208690 077420870 0774208870 0774208890 077420530 0774208892 0774205780 0774208892 0774206832 0774208892 0774205786 0774208892 0774208994 0774206334 0774208592 0774208780 0774208882 0774208998 077420530 0774208590 077420770 0774208890 0774208998	7/76800/38 0/76801/42 0/76800/38 0/76800/39 0/76800/38 0/76800/38 0/76800/39	13 - 14 - 14 - 14 - 14 - 14 - 14 - 14 -
0774206538 0774206558 077420672 0774206886 0774207000 0774206600 0774206660 077420674 077420672 0774206542 077420682 0774207674 077420688 0774207002 0774206542 0774206652 0774207678 0774206892 0774207006	777849038 0778490152 0778490266 0778490380 077849049 0778490608 7778490040 0778490154 0778490286 0778490382 077849049 0778490610 7778490042 0778490156 0778490270 0778490349 077849049 0778490610 7778490042 0778490156 0778490270 0778490346 077849050 0778490612 7778490044 0778490158 0778490272 0778490386 077849050 0778490614	THE PERSON NAMED IN COLUMN NAM
0774206546 0774206666 0774206780 0774206894 0774207006 0774206546 0774206668 0774206782 0774206780 0774207010 0774206500 0774206670 0774206784 0774206898 0774207012 0774206502 077420672 0774206786 0774206890 0774207014 0774206502 077420672 0774206786 0774206800 0774207014	1779460046 0779460160 0778460274 0777460398 0779460072 0778460016 0779460074 0778460074 0778460074 0778460074 0778460074 0778460074 077846074 0778	
0774206556 0774206676 0774206793 0774205904 0774207018 0774206558 0774206678 0774206792 0774206906 0774207020 0774206650 0774206678 0774206792 0774206906 0774207020 0774206600 0774206690 0774206909 0774206901 0774207022	7778490056 0778490170 0778490284 0778490389 077849012 0778480626 7778490356 0778490170 0778490284 0778490389 077849012 0778480626 7778490360 0778490172 0778490286 077849000 077849011 0778490626 7778490360 0778490174 0778490280 077849040 0778490518 0778490630 7778490362 0778490176 0778490290 0778490494 0778490518 0778490630	
0774206564 0774206884 0774206788 0774206912 0774207026 0774206696 0774206696 0774206893 0774206931 0774207028 0774206696 0774206898 0774206893 0774207020 0774206570 0774206690 0774206804 0774207032	7778480064 0778480176 0778480292 0778480406 0778480520 0778480634 7778480066 0778480180 0778480294 0778480680 0778480522 0778480656 7778480058 0778480182 0778480296 0778480501 0778480524 0778480658 77784800970 0778480184 0778480298 0778480412 0778480526 0778480640	
0774206572 0774206992 0774206980 0774206920 0774207034 0774206574 0774206894 07742088808 077420822 0774207036 0774206576 0774206896 0774208910 0774208924 0774207036 0774206578 0774206898 0774208912 0774208926 0774207040	1778480072 077840186 0778400000 0778400414 0778460028 0778460642 1077840074 0778400180 0778400026 077840016 0778400016 077840016 0778400016 0778400016 0778400016 0778400016 0778400016 0778400016 077840016 077840016 077840016 077840016 077840016 077840018 077840016 077840016 077840016 077840016 077840016 077840016 077840016 077840016 077840016 077840016 077840016 077840016 077840018 0	
0774205682 0774205702 0774205816 0774205830 0774207042 0774205854 0774205704 0774205816 0774205832 0774207046 0774205954 0774205706 0774205810 0774205832 0774207048 0774205959 0774205706 0774205822 0774205934 0774207050	7778460082 0778460196 0778460310 07784602424 0778460538 0778460652 7778460082 0778460396 0778460310 0778460340 0778460540 0778460652 7778460080 0778460300 0778460312 0778460340 0778460540 0778460666 7778460080 0778460200 0778460314 0778460430 0778460540 0778460666 7778460088 0778460200 0778460316 0778460430 0778460544 0778460666	
0774206996 0774206710 0774206824 0774206936 0774207002 0774206996 0774206722 0774206826 0774206964 0774206964 077420690 07742070064 077420690 0774207014 077420690 0774206716 077420690 0774206716 077420690 0774206716 077420690 077420690 077420690 0774206916 077420690	2778480090 0778480204 0778480318 0778480432 0778480546 0778480660 2778480092 0778480200 0778480320 077848034 077848058 0778480660 077840909 077840090 077848032 077840936 0778480909 077848064 2778480908 0778480210 0778480324 0778480438 0778480505 077848064 2778480096 0778480210 0778480324 0778480438 0778480552 0778480666	
0774206004 0774206718 0774206832 0774206846 0774207060 07742070600 0774206720 0774206830 0774207602 0774206008 077420720 0774206830 0774206830 0774207064 077420610 0774206724 0774206830 0774206830 0774207066 0774206110 0774206724 0774206830 0774206852 0774207066	\$\text{177846006} \text{977846034} \text{9778460668} \text{977846054} \text{977846054} \text{9778460568} \text{9778460074} \text{9778460074} \text{977846074} \text{977846074} \text{977846074} \text{977846074} \text{977846074} \text{977846076} \text{977846074} \text{977846074} \text{977846074} \text{977846074} \text{977846074} \text{977846074} \text{977846074} \text{977846074} \text{977846074} \text{977846074} \text{977846074} \text{977846074} \text{977846074} \text{977846074} \text{977846074} \text{977846074} \text{977846074} 97784	
0774206814 0774206726 0774206805 0774206805 0774206805 0774206805 0774206805 0774206805 0774206805 0774206805 0774206806 077420680 077420	7778480106 7778400228 0778400336 0776400550 0776405664 0776406767 777840110 077840222 0778400338 0776400550 0776405664 0776406767 777840110 077840222 077840338 0778400322 077840566 077640566 0776406682 777840112 077840226 077840340 0778409456 077640566 0776406882	
0774206822 0774206736 0774206850 0774206964 077420624 0774206738 0774206852 0774206966 077420628 077420670 0774206865 0774206868 0774206028 0774206742 0774206856 0774206870	0778480118 0778480230 0778480344 0778480458 0778480572 0778480686 0778480118 0778480232 0778490346 0777849060 0777480574 0778480686 0778480120 0778480234 0778480348 0778480642 0778480576 0778480690 0778480122 0778480234 0778480350 0778490464 0778480578 0778480690 0778480122 0778480358 0778480350 0778490464 0778480578 0778480692	
0774206630 0774206744 0774206858 0774206872	7778480124 0778480238 0778480352 0778480486 0778480590 0776480694	
		MM 25-0745 GENERAL DEVELOPMENT PLAN RHODINE BORROW PIT &
		THE GROVE PARCELS PD
		Text Context Text
		Territoria und Octop, 1.4. Territoria del Conjun, 1.5. Territoria del Conjunt
		, , , , , , , , , , , , , , , , , , , ,

APPLICATION NUMBER: MM 25-0745

ZHM HEARING DATE: July 21, 2025

BOCC LUM MEETING DATE: September 9, 2025 Case Reviewer: Jared Follin

9.0 FULL TRANSPORTATION REPORT (see following pages)

AGENCY REVIEW COMMENT SHEET

DATE, 7/15/2025

TO: Z	Coning Technician, Development Services Department	nent	A1E. //13/2023
REVI	EWER: Richard Perez, AICP, Executive Planner	AGENCY/DEPT: Transpo	ortation
PLAN	NNING AREA/SECTOR: Boyette	PETITION NO: MM 2	.5-0745
	This agency has no comments.		
	This agency has no objection.		
X	This agency has no objection, subject to the liste	ed or attached conditions.	
	This agency objects for the reasons set forth belo	ow.	

CONDITIONS OF ZONING APPROVAL

(Applicable only to the East Grove Development Area)

New Conditions:

 Notwithstanding the access shown on the PD site plan to the Park Tract under County ownership, existing and any proposed future access(es) shall comply with the County Land Development Code requirements.

Revised Conditions:

- 22. The developer shall construct the following site access improvements, of which 1.a., 1.b. or 1.c. shall be constructed only if warranted per Section 6.04.04.D. of the Hillsborough County Land Development Code or unless otherwise approved in accordance the Section 6.04.02.B. administrative variance process:
 - a. An eastbound to southbound right turn lane on CR 672 at Shelley Ln.; [COMPLETED]
 - b. A westbound to southbound left turn lane on CR 672 at Shelley Ln.; [COMPLETED]
 - c. A southbound to eastbound left turn lane <u>and a northbound to eastbound right turn</u> lane on Balm Wimauma Rd. into the project's southernmost entrance; and,
 - d. A southbound to eastbound left turn lane and a northbound to eastbound right turn lane on Balm Wimauma Rd. into the project's New Jade Ave. entrance; and, One (1) of the following options (as depicted on the on the PD site plan) relating to site access and roadway reconfigurations proposed by the developer. :
 - i. Option 1 The developer shall construct an extension of Balm Wimauma Rd. (between its intersection with Balm Rd. and CR 672) as a 2-lane collector roadway. Within 6 months of acceptance of the roadway extension, the developer shall remove up to a +/-1,300 foot long segment of existing Balm Wimauma Rd. south of CR 672. Specific limits of the segment to be removed shall be determined and approved by Hillsborough County Public Works. Utilization of this option is contingent upon the developer's ability to, at its sole cost, design the facility, obtain all required permits for construction, and acquire any additional right of way necessary for the proposed extension and related improvements. Utilization of this option is also contingent upon review and approval of the proposed roadway by Hillsborough County Public Works, including any turn lanes that may be required by the County at the intersection of the roadway extension with CR 672. In no event shall removal of the roadway section occur until such time as a

ii.

- e. Option 2— The developer shall realign up to +/- 1,300 feet of Balm Wimauma Rd. (i.e. that portion immediately south of CR 672) such that it connects to Shelley Concurrent with the opening of the realigned roadway extension, the developer shall close the old/realigned roadway and, within 6 months, complete removal of the old/unutilized roadway. Specific limits of the segment to be realigned/removed shall be determined and approved by Hillsborough County Public Works. Utilization of this option is contingent upon the developer's ability to, at its sole cost, design the facility, obtain all required permits for construction, and acquire any additional right-of-way necessary for the proposed extension and related improvements. Utilization of this option is also contingent upon review and approval of the proposed roadway by Hillsborough County Public Works, including any turn lanes that may be required by the County at the newly created intersection of Balm Wimauma Rd. and Shelley Ln. The applicant shall also be responsible for preserving sufficient right-of-way necessary to accommodate a 2lane enhanced roadway segment between the new intersection and CR 672. [THIS CONDITION HAS BEEN SATISFIED]
- iii. Option 3 The developer shall construct a roundabout at the intersection of CR 672, Balm Wimauma Rd., Shelley Ln., and Balm Boyette Rd. This option may require the developer to dedicate or otherwise acquire additional right of way necessary to accommodate the roundabout. Notwithstanding anything herein to the contrary, utilization of this option shall relieve the developer of its obligation to construct the improvements listed in 1.a. and 1.b., above. Utilization of this option is also contingent upon review and approval of the proposed roundabout by Hillsborough County Public Works.
- 23. As Shelley Ln. is a substandard local roadway the developer will be required to improve Shelley Ln., between its southernmost access connection and CR 672 the intersection with Balm-Wimauma Rd., to current County standards unless otherwise approved in accordance with Section 6.04.02.B. of the Hillsborough County LDC. Deviations from TTM standards may be considered in accordance with Section 1.7.2. and other applicable sections of the Hillsborough County TTM.
- As Balm Wimauma Rd. may be a substandard collector roadway, the developer will be required to coordinate with Hillsborough County Public Works to determine the improvements that may be required prior to or concurrent with plat/site/construction plan approval. If MM 25-0745 is approved, the County Engineer will approve the Design Exception (dated July 9, 2025), which was found approvable on July 11, 2025, for Balm Wimauma Rd. substandard road improvements. As Balm Wimauma Rd. is a substandard rural collector roadway, the developer will be required to construct improvements that include 11-foot-wide lanes, 8-foot shoulders with 7 feet paved consistent with the Design Exception.

PROJECT SUMMARY AND ANALYSIS

The applicant is requesting to modify the East Grove portion of the PD 18-0304, as most recent amended by PRS 23-0030, approved for 5,535 s.f. of commercial uses and 410 single-family detached dwelling units. The request is to eliminate the commercial uses and allow for a maximum of 700 single family detached dwelling units. Additionally, the revised PD site plan removes the inset re-alignment options for Balm Wimauma Rd. which was recently completed with the construction of initial Balm Grove East residential subdivision plat.

The Rhodine Borrow Pit development area is not part of this proposed PD modification.

The applicant submitted a trip generation and site access analysis as required by staff. Since the project will potentially generate more than 50 peak hour trips at buildout, a detailed transportation analysis is required per the Development Review Procedures Manual (DRPM). Staff has prepared a comparison of the trips potentially generated under the existing and proposed zoning designations, utilizing a generalized worst-case scenario. The information below is based on data from the Institute of Transportation Engineer's Trip Generation Manual, 11th Edition.

Approved Uses in the PD Modification Area:

Land Use/Size	24 Hour Two-	Total Peak Hour Trips	
	Way Volume	AM	PM
PD, 410 Single-Family Detached Dwelling Units (ITE Code 210)	3,808	296	394
PD, 5,000 s.f. Commercial Uses (ITE Code 822)	272	12	48
Total:	4,080	308	442

Proposed Uses in Modification Area:

Land Use/Size	24 Hour Two- Way Volume	Total Peak Hour Trips	
		AM	PM
PD, 700 Single-Family Detached Dwelling Units (ITE Code 210)	6,045	438	619

Trip Generation Difference:

	24 Hour Two- Way Volume	Total Peak Hour Trips	
		AM	PM
Change:	+1,965	+130	+177

TRANSPORTATION INFRASTRUCTURE SERVING THE SITE

<u>CR 672</u> is a 2-lane, undivided, arterial roadway characterized by +/- 12-foot wide travel lanes with +/-5-foot paved shoulders in good condition. The roadway lies within a variable width right-of-way (+/- 80 feet along the project's frontage). There are bicycle facilities (on paved shoulders) present along a portion of CR 672 in the vicinity of the proposed project. There are no sidewalks along CR 672 in the vicinity of the proposed project.

Balm Wimauma Rd. is a 2-lane, undivided, collector roadway characterized by +/- 11-foot wide lanes with 7-foot bike lanes in good condition. The roadway segment north of the intersection with Balm Rd. lies within a +/- 64 to 86 feet wide right-of-way and has curb and gutter on both sides. This segment has sidewalk on the south side with the exception of the +/-1,250 feet east and north of the Balm Park and Community Center driveway where sidewalks are located on both sides. South of the intersection with Balm Rd. the roadway lies within +/-62 to 84 feet of right of way. There are no curb and gutter and only a portion has sidewalk present on the east side of the road. Therefore, there are portions of the roadway that are deemed substandard.

Balm Wimauma Rd. is shown on Hillsborough County Corridor Preservation Plan as a future 2-lane enhanced roadway.

<u>Balm Rd.</u> is a 2-lane collector roadway characterized by +/- 11 foot lanes in good condition. The roadway lies within a +/- 62 to 100-foot wide right-of-way. There is a sidewalk on the south side and bicycle facilities on both sides in the vicinity of the proposed project.

<u>Shelley Ln.</u> is a 2-lane, local roadway characterized by +/- 20-feet of pavement in good condition within +/-60 feet of right of way. There is a 5-foot sidewalks on the east side of the roadway.

SITE ACCESS

The project is taking access to Balm Wimauma Rd. and Shelley Ln. Additional vehicular and pedestrian access connections are proposed to stub out to folio# 77847.0000 and 77847.0025 for future connection in the event said properties redevelop.

The applicant's detailed site access analysis finds that southbound to eastbound left turn lanes are warranted at the two proposed access connections to Balm Wimauma Rd. Additionally, the applicant is proposing to construct northbound to eastbound right turn lanes at Balm Wimauma Rd. access connections.

REQUESTED DESIGN EXCEPTION: BALM WIMAUMA RD.

As Balm Wimauma Rd. is a substandard collector roadway, the applicant's Engineer of Record (EOR) submitted a Design Exception request for the roadway (dated July 9, 2025) to determine the specific improvements that would be required by the County Engineer. Based on factors presented in the Design Exception request, the County Engineer found the Design Exception request approvable (on July 11, 2025). The developer will be required to construct 11-foot-wide lanes, 8-foot shoulders with 7 feet paved consistent with the Design Exception.

If this zoning is approved, the County Engineer will approve the Design Exception request.

LEVEL OF SERVICE DATA

Roadway	From	То	LOS Standard	Peak Hour Directional LOS
Balm Wimauma Rd.	SR 674	CR 672	С	В
CR 672	Balm Boyette Rd.	CR 39	D	В
Balm Rd./ CR 672	US 301	Balm Riverview Rd.	D	В

Source: Hillsborough County 2020 Level of Service Report.

From: Williams, Michael [WilliamsM@hcfl.gov]

Sent: Friday, July 11, 2025 12:43 PM **To:** Steven Henry [shenry@lincks.com]

CC: Kami Corbett [kami.corbett@hwhlaw.com]; anna.ritenour@clearviewland.com; Follin,

Jared [FollinJ@hcfl.gov]; Perez, Richard [PerezRL@hcfl.gov]; Drapach, Alan [DrapachA@hcfl.gov]; Tirado, Sheida [TiradoS@hcfl.gov]; De Leon, Eleonor

[DeLeonE@hcfl.gov]; PW-CEIntake [PW-CEIntake@hcfl.gov]

Subject: FW: MM 25-0745 - Design Exception Review

Attachments: 25-0745 DEAd 07-10-25.pdf

Steve,

I have found the attached Design Exception (DE) for PD 25-0745 APPROVABLE.

Please note that it is you (or your client's) responsibility to follow-up with my administrative assistant, Eleonor De Leon (<u>DeLeonE@hcfl.gov</u> or 813-307-1707) after the BOCC approves the PD zoning or PD zoning modification related to below request. This is to obtain a signed copy of the DE/AV.

If the BOCC denies the PD zoning or PD zoning modification request, staff will request that you withdraw the AV/DE. In such instance, notwithstanding the above finding of approvability, if you fail to withdraw the request, I will deny the AV/DE (since the finding was predicated on a specific development program and site configuration which was not approved).

Once I have signed the document, it is your responsibility to submit the signed AV/DE(s) together with your initial plat/site/construction plan submittal. If the project is already in preliminary review, then you must submit the signed document before the review will be allowed to progress. Staff will require resubmittal of all plat/site/construction plan submittals that do not include the appropriate signed AV/DE documentation.

Lastly, please note that it is critical to ensure you copy all related correspondence to PW-celntake@hcfl.gov

Mike

Michael J. Williams, P.E.

Director, Development Review County EngineerDevelopment Services Department

P: (813) 307-1851 M: (813) 614-2190 E: <u>Williamsm@HCFL.gov</u>

W: HCFLGov.net

Hillsborough County

601 E. Kennedy Blvd., Tampa, FL 33602

Facebook | Twitter | YouTube | LinkedIn | HCFL Stay Safe

Please note: All correspondence to or from this office is subject to Florida's Public Records law.

From: Tirado, Sheida <TiradoS@hcfl.gov> Sent: Friday, July 11, 2025 10:56 AM

To: Williams, Michael < Williams M@hcfl.gov>

Cc: Perez, Richard < Perez RL@hcfl.gov>; Drapach, Alan < DrapachA@hcfl.gov>

Subject: RE: MM 25-0745 - Design Exception Review

Hello Mike,

The attached Design Exception is Approvable to me, please include the following people in your response email:

shenry@lincks.com kami.corbett@hwhlaw.com anna.ritenour@clearviewland.com follinj@hcfl.gov perezrl@hcfl.gov drapacha@hcfl.gov

Best Regards,

Sheida L. Tirado, PE

Transportation Review & Site Intake Manager

Development Services Department

E: TiradoS@HCFL.gov

P: (813) 276-8364 | M: (813) 564-4676

601 E. Kennedy Blvd., Tampa, FL 33602

HCFL.gov

<u>Facebook</u> | <u>X</u> | <u>YouTube</u> | <u>LinkedIn</u> | <u>Instagram</u> | <u>HCFL Stay Safe</u>

Hillsborough County Florida

Please note: All correspondence to or from this office is subject to Florida's Public Records law.

From: Tirado, Sheida

Sent: Friday, July 4, 2025 12:45 PM

To: Williams, Michael < Williams M@hcfl.gov >

Cc: Perez, Richard < PerezRL@hcfl.gov>; Drapach, Alan < DrapachA@hcfl.gov>

Subject: MM 25-0745 - Design Exception Review

Hello Mike,

The attached Design Exception is Approvable to me, please include the following people in your response email:

shenry@lincks.com kami.corbett@hwhlaw.com anna.ritenour@clearviewland.com follinj@hcfl.gov perezrl@hcfl.gov drapacha@hcfl.gov

Best Regards,

Sheida L. Tirado, PE

Transportation Review & Site Intake Manager

Development Services Department

E: <u>TiradoS@HCFL.gov</u>

P: (813) 276-8364 | M: (813) 564-4676

601 E. Kennedy Blvd., Tampa, FL 33602

HCFL.gov

Facebook | X | YouTube | LinkedIn | Instagram | HCFL Stay Safe

Hillsborough County Florida

Please note: All correspondence to or from this office is subject to Florida's Public Records law.



Supplemental Information for Transportation Related Administrative Reviews

Instructions:

- This form must be provided separately for each request submitted (including different requests of the same type).
- This form must accompany all requests for applications types shown below. Staff will not log in or assign cases that are not accompanied by this form, or where the form is partially incomplete.
- A response is required in every field. Blank fields or non-responsive answers will result in your application being returned.
- All responses must be typed.
- Please contact Eleonor de Leon at <u>deleone@HCFL.gov</u> or via telephone at (813) 307-1707 if you have questions about how to complete this form.

to complete this form:	
Request Type (check one)	 Section 6.04.02.B. Administrative Variance ★ Technical Manual Design Exception Request Alternative Parking Plan Request (Reference LDC Sec. 6.05.02.G3.) Request for Determination of Required Parking for Unlisted Uses (Reference LDC Sec. 6.05.02.G.1. and G.2.)
Submittal Type (check one)	☐ New Request ☐ Additional Information
Submittal Number and Description/Running History (check one and complete text box using instructions provided below)	 ×1. Balm-Wimauma Road - Substandard Road
submittal number/name to each separate request. number previously identified. It is critical that the ap	riests (whether of the same or different type), please use the above fields to assign a unique Previous submittals relating to the same project/phase shall be listed using the name and uplicant reference this unique name in the request letter and subsequent filings/correspondence. I information related to a previously submitted request, then the applicant would check the
Project Name/ Phase Balm East	
Important: The name selected must be used on all fulf request is specific to a discrete phase, please also	iture communications and submittals of additional/revised information relating to this variance. list that phase.
numbers must be provided in the format provided b	Check This Box If There Are More Than Five Folio Numbers to a maximum of five. If there are additional folios, check the box to indicate such. Foliony the Hillsborough County Property Appraiser's website (i.e. 6 numbers, followed by a hyphen,
followed by 4 additional numbers, e.g. "012345-67" 054321-9876").	789"). Multiple records should be separated by a semicolon and a space e.g. "012345-6789;
Name of Person Submitting Request	Steven J. Henry, P.E.
Important: All Administrative Variances (AV) and De State of Florida.	esign Exceptions (DE) must be Signed and Sealed by a Professional Engineer (PE) licensed in the
Current Property Zoning Designation	
Designation. Typing "N/A" or "Unknown" will result i County Zoning Atlas, which is available at https://mc	mily Conventional – 9" or "RMC-9". This is not the same as the property's Future Land Use (FLU) in your application being returned. This information may be obtained via the Official Hillsborough aps.hillsboroughcounty.org/maphillsborough/maphillsborough.html. For additional assistance, for Development Services at (813) 272-5600 Option 3.
Pending Zoning Application Number	East 25-0745
	ter the application number proceeded by the case type prefix, otherwise type "N/A" or "Not IM for major modifications, PRS for minor modifications/personal appearances.
Related Project Identification Number (Site/Subdivision Application Number)	N/A

1 of 1

Important: This 4-digit code is assigned by the Center for Development Services Intake Team for all Certified Parcel, Site Construction, Subdivision

Construction, and Preliminary/Final Plat applications. If no project number exists, please type "N/A" or "Not Applicable".

03/2025



July 9, 2025

Mr. Michael Williams, PE County Engineer Development Review Director Hillsborough County 601 East Kennedy Blvd., 20th Floor Tampa, FL 33602

Re: Balm East – PD 25-0745 Folio: See Appendix

Lincks Project No. 19187

The purpose of this letter is to request a Design Exception to the Hillsborough County Transportation Technical Manual per Section 1.7.2 to meet Land Development Code Section 6.04.03L for Balm-Wimauma Road from Balm Road to the southern property line.

The subject property is currently zoned PD to allow the following uses:

- Single Family 356 Dwelling Units
- Retail 5,000 Square Feet

The developer proposes to amend the PD to allow the following land use:

Single Family – 700 Dwelling Units

Table 1 provides the trip generation for the approved and proposed project.

The access for the project is proposed to include the following:

- Two (2) full accesses to Balm-Wimauma Road
- Shelley Lane south of the realigned Balm-Wimauma Road

The proposed PD plan is included in the Appendix of this letter.

The subject site is within the Hillsborough County Urban Service Area. According to the Hillsborough County Roadways Functional Classification Map, Balm-Wimauma Road is a collector road.

Balm-Wimauma Road from Balm Road to Balm Gardens Lane has been improved by the developer with the following section:

Eleven (11) foot lanes

5023 West Laurel Street Tampa, FL 33607 813 289 0039 Telephone 8133 287 0674 Telefax www.Lincks.com Website Mr. Mike Williams July 9, 2025 Page 2

- Eight (8) foot shoulders with seven (7) feet paved
- Five (5) foot sidewalks along the property frontage

The request is for a Design Exception to TS-7 of the Hillsborough County Transportation Technical Manual for Balm-Wimauma Road. The segment of Balm-Wimauma Road from Balm Gardens Lane to the southern property line or the limit of the access improvements, whichever is further, is as follows:

- Eleven (11) foot lanes
- Eight (8) foot shoulders with seven (7) feet paved

The following exceptions are requested to accommodate the proposed project:

- Lane Width TS-7 has 12 foot lanes. The existing roadway has 11 foot lanes.
- 2. Shoulder TS-7 has 8 foot shoulder with 5 foot paved. The existing road has limited paved shoulders.
- 3. Sidewalk TS-7 has five (5) foot sidewalk on both sides of the road. There are no sidewalks south of the subject property.

The justification for the Design Exception is as follows:

- 1. The Developer proposes to improve Balm-Wimauma Road from the southern property line or the limits of the access improvements, whichever is further.
 - Eleven (11) foot lanes
 - Eight (8) foot shoulders with seven (7) foot paved
 - Construct turn lanes as warranted
 - Construct five (5) foot sidewalks along the property frontage

Figure 1 provides the proposed typical section.

Based on the above, it is our opinion, the proposed improvements to Balm-Wimauma Road will offset the impact of the project and meet the intent of the Transportation Technical Manual to the extent feasible.


Mr. Mike Williams July 9, 2025 Page 3

Please do not hesitate to contact us if you have information.	STE LICENSE 1
Best Regards	* No. 51555
Steven J Henry	GA E OF
President	O COMPANDA CALL
Lincks & Associates, LLC A TMC Company	WAL EN
P.E. #51555	
Based on the information provided by the app	olicant, this request is:
Disapproved	
Approved	
Approved with Condition	s
If there are any further questions or you need L. Tirado, P.E, (813) 276-8364, TiradoS@hillsb	. ·
	Sincerely,
	Michael J. Williams
	Hillsborough County Engineer

IABLE 1 ESTIMATED PROJECT TRIP ENDS (1)

our	Total	343	117	<u>26</u>	486	328	48	376	862	906	619	1,525	155	1,366
PM Peak Hour	Trip Ends	127	28	22	207	121	24	145	352	335	229	564	44	520
PM		216	59	41	279	207	24	231	510	571	390	961	111	850
onr	Total	247	42	25	314	237	12	249	563	633	438	1,071	123	948
AM Peak Hour	Trip Ends	185	17	ကျ	205	178	12	183	388	475	328	803	92	711
AN	드	62	25	22	109	59	7	99	175	158	110	268	31	237
3	Daily Trip Ends	3,388	963	118	4,469	3,245	272	3,517	7,986	8,778	6,045	14,823	1,705	13,118
	Size	373 DU's	17,692 SF	10,863 SF	Sub-Total	356 DU's	5,000 SF	Sub-Total	Total	1,050 DU's	700 DU's	Sub-Total	204 DU's	Net Increase
ļ		210	822	710		210	822			210	210		210	
	Land Use	Single Family	Retail	Office		Single Family	Retail			Single Family	Single Family		Single Family	
	Project	Balm West				Balm East				Balm West	Balm East		Balm West	
	Status	Approved				Approved				Proposed			Existing	


(1) Source: ITE Trip Generation Manual, 11th Edition, 2021.




TYPICAL SECTION BALM-WIMAUMA ROAD


REVISED: 07/10/25

FIGURE 1
TYPICAL SECTION



Development Sen	
DALMEACT	
BALM EAST PD PLAN	
LINCKS & ASSOCIATES, A TMC Company	





Received July 10, 2025 Development Services Clearview LAND DESIGN, P.L. MM 25-0745
GENERAL DEVELOPMENT PLAN
RHODINE BORROW PIT & THE GROVE PARCELS PD SCALE: 1" = 200' SAWN CITATION OHICKED DELICATION OF THE PARTY OF THE PART JSH SOUTHFORK
DEVELOPMENT LLC
III SAmmenia Ave, Suitecon
Tampa, Florida 33609
(813) 767-5783 60°± RIGHT OF WAY
 20°± ASPHALT PAVEMENT / 2 LANES
 LOCAL ROAD
 ASPHALT IN GOOD CONDITION SINGLE FAMILY DETACHED LOT C.R. 672 (BALM RIVER ROAD) SCHOOL STATE nam rear setback of 5 feet for and 3 feet for pool enclosure 67½ BIGHT OF WAY
 29½ ASPHALT PAYEMENT /
 COLLECTOR BOAD
 ASPHALT IN GOOD CONDITION BALM WIMAUMA ROAD MARRIED UNITED 2 SHELLEY ROAD 4 BALM ROAD Monthly Report of the Court of R.O.W DEDICATION POTENTIAL R.O.W. CROSS SECTION D NITS --30' ENHANCED LANDSCAPE BUFFER En Clearwing. P.L. A. Clearwing. P.L. A. O. Clearwine Land Design. P.L. A. 2010 W. Azeele Street, Saite 150 at Tompo, R. 33609 ft. (813) 223-3910 ft. Legal Counet Hill Ward Henderson 101 E. Kernedy Blvd., Suite 37 Tompo, R. 33602 (813) 221-3900 088698-7510
BISCHHOWER PROFERTY
GROVE LLC
FILL
RES-4
LINERTY TRIREDS. 088698-7510 BSRNHOWER OFERTY GROUP LLI 088698-7200 SHELLEY LANG THE 088698-7201 BAIM GROVE LLC MC CULLOUGH A L; MC CULLOUGH A L; MCCULLOUGH VIVIA RES-4 RES-4 RES-4 4 C.R. 672 (BALM RIVER ROAD) EXISTING
BALM GROVE EAST
SUBDIVISION
PLATBOOK 148 PAGE 2 O77854-0000 HBLISBORCOUGH COUNTY THE TOWNS OFFET 150' ZONING OFFSET SINGLE FAMILY
DETACHED RES-4 N77842-0000BUTLER -RECHALD R, BUTLER -EYVONNE B 077882-0025 BALM GROVE LLC 077841-0200 BENITEZ EJAINA R RES-4 GAOS AMUAMIW MIAS RES-4 RES.4 PARABAY 0718% 0928 (ISBNOWER PROPERTY RES-4
RES-6
RES-6 RES-4 III 077880-0200 VERA GUADALUPE 4 BALM ROAD


Son, particoses enemanaved Son, particoses, enemanaved Total representations of the participant of const.	BORROW PIT & BORROW PIT & BY PARCEL BY PARCEL BY PARCEN BY PA	RHODINE THE GE Call before Security A 9 of
THE GROVE PARCEL LEGAL DESCRIPTION: LEGAL DESCRIPTION; (PRE COMPITTIENT TO STATE AND	AND CONTRIBUTE OF THE MELECONTRIBUTE OF A PRINCIPLE OF THE MENT OF	18 - 03.0 4 APP # RZ-PD 18-0304 RV
	Septiminal bits by control table for the discrete of the section is committed to the control table of table of the control table of table of the control table of tab	


MM 25-0745
GENERAL DEVELOPMENT PLAN
RHODINE BORROW PIT &
THE GROVE PARCELS PD


Clearview LAND DESIGN, P.L.


JSH SOUTHFORK
DEVELOPMENT LLC
III SAmenia Ave. Suitezon
Tampa. Horida 33609
(813) 767-5783

ANDOINE AND	-				THE GROVE LARGE	ا۔		- 1			
	0100001110	0240004400	000000000000000000000000000000000000000		FOLIOS	MM Affected	d Parcel -		0778480708		
0774206514	0774206614	0774206748	0774206862	0774208974	0778480012	0778480126	0778480240		07/8480354 07/8480468	0778480582	0778480696
	0774206636	0774206750	0774206864	0774206978	0778480016	0778480130	0778480244	0778480358	0778480470	0778480586	0778480700
	0774206638	0774206752	0774206866	0774206980	0778480018	0778480132	0778480246	0778480360	0778480474	077848058B	0778480700
-	0774206640	0774206754	0774206868	0774206982	0778480020	0778480134	0778480248	0778480362	0778480476	0778480590	0778480704
0774206522	0774206642	0774206756	0774206870	0774206984	0778480022	0778480136	0778480250	0778480364	0778480478	0778480592	0778480706
ш	0774206644	0774206758	0774206872	0774206986	0778480024	0778480138	0778480252	0778480366	0778480480	0778480594	0778480710
0774206528	0774206646	0774206760	0774206874	0774206988	0778480026	0778480140	0778480254	0778480368	0778480482	0778480596	
0774206528	0774206648	0774206762	0774206876	0774206990	0778480028	0778480142	0778480256	0778480370	0778480484	0778480598	
0774206530	0774206650	0774206764	0774206878	0774206992	0778480030	0778480144	0778480258	0778480372	0778480486	0778480600	
0774206532	0774206652	0774206766	0774206880	0774206994	0778480032	0778480146	0778480260	0778480374	0778480488	0778480602	
0774206534	0774206654	0774206768	0774206882	0774206996	0778480034	0778480148	0778480262	0778480376	0778480490	0778480604	
0774206536	0774206656	0774206770	0774206884	0774206998	0778480036	0778480150	0778480264	0778480378	0778480492	0778480606	
0774206538	0774206658	0774206772	0774206886	0774207000	0778480038	0778480152	0778480266	0778480380	0778480494	0778480608	
0774206540	0774206660	0774206774	0774206888	0774207002	0778480040	0778480154	0778480268	0778480382	0778480496	0778480610	
0774206542	0774206662	0774206776	0774206890	0774207004	0778480042	0778480156	0778480270	0778480384	0778480498	0778480612	
0774206544 (0774206664	0774206778	0774206892	0774207006	0778480044	0778480158	0778480272	0778480386	0778480500	0778480614	
0774206546	0774206666	0774206780	0774206894	0774207008	0778480046	0778480160	0778480274	0778480388	0778480502	0778480616	
0774206548 (0774206668	0774206782	0774206896	0774207010	0778480048	0778480162	0778480276	0778480390	0778480504	0778480618	
0774206550 (0774206670	0774206784	0774206898	0774207012	0778480050	0778480164	0778480278	0778480392	0778480506	0778480620	
0774206552	0774206672	0774206786	0774206900	0774207014	0778480052	0778480166	0778480280	0778480394	0778480508	0778480622	
	0774206674	0774206788	0774206902	0774207016	0778480054	0778480168	0778480282	0778480396	0778480510	0778480624	
0774206556	0774206676	0774206790	0774206904	0774207018	0778480056	0778480170	0778480284	0778480398	0778480512	0778480626	
	0774206678	0774206792	0774206906	0774207020	0778480058	0778480172	0778480286	0778480400	0778480514	0778480628	
_	0774206680	0774206794	0774206908	0774207022	0778480060	0778480174	0778480288	0778480402	0778480516	0778480630	
_	0774206682	0774206796	0774206910	0774207024	0778480062	0778480176	0778480290	0778480404	0778480518	0778480632	
_	0774206684	0774206798	0774206912	0774207026	0778480064	0778480178	0778480292	0778480406	0778480520	0778480634	
_	0774206686	0774206800	0774206914	0774207028	0778480066	0778480180	0778480294	0778480408	0778480522	0778480636	
_	0774206688	0774206802	0774206916	0774207030	0778480068	0778480182	0778480296	0778480410	0778480524	0778480638	
-	0774206690	0774206804	0774206918	0774207032	0778480070	0778480184	0778480298	0778480412	0778480526	0778480640	
_	0774206692	0774206806	0774206920	0774207034	0778480072	0778480186	0778480300	0778480414	0778480528	0778480642	
	0774206694	0774206808	0774206922	0774207036	0778480074	0778480188	0778480302	0778480416	0778480530	0778480644	
_	0774206696	0774206810	0774206924	0774207038	0778480076	0778480190	0778480304	0778480418	0778480532	0778480646	
	0774206698	0774206812	0774206926	0774207040	0778480078	0778480192	0778480306	0778480420	0778480534	0778480648	
_	0774206700	0774206814	0774206928	0774207042	0778480080	0778480194	0778480308	0778480422	0778480536	0778480650	
_	0774206702	0774206816	0774206930	0774207044	0778480082	0778480196	0778480310	0778480424	0778480538	0778480652	
	0774206704	0774206818	0774206932	0774207046	0778480084	0778480198	0778480312	0778480426	0778480540	0778480654	
-	0774206706	0774206820	0774206934	0774207048	0778480086	0778480200	0778480314	0778480428	0778480542	0778480656	
	0774206708	0774206822	0774206936	0774207050	0778480088	0778480202	0778480316	0778480430	0778480544	0778480658	
07/4206596	0774206710	07/4206824	0774206938	0774207052	0778480090	0778480204	0778480318	0778480432	0778480546	0778480660	
-	0774206712	0774206828	0774206940	0774207054	0778480092	0778480208	0778480320	0778480434	0778480548	0778480662	
-	0774206716	0774206830	0774206944	0774207058	0778480096	0778480210	0778480324	0778480438	0778480550	0778480666	
-	0774206718	0774206832	0774206946	0774207060	0778480098	0778480212	0778480126	0778480440	0778480554	0778480668	
+	0774206720	0774206834	0774206948	0774207062	0778480100	0778480214	0778480328	0778480442	0778480556	0778480670	
	0774206722	0774206836	0774206950	0774207064	0778480102	0778480216	0778480330	0778480444	0778480558	0778480672	
0774206610 (0774206724	0774206838	0774206952	0774207066	0778480104	0778480218	0778480332	0778480446	0778480560	0778480674	
0774206612 (0774206726	0774206840	0774206954		0778480106	0778480220	0778480334	0778480448	0778480562	0778480676	
0774206614 (0774206728	0774206842	0774206956		0778480108	0778480222	0778480336	0778480450	0778480564	0778480678	
	0774206730	0774206844	0774206958		0778480110	0778480224	0778480338	0778480452	0778480566	0778480680	
	0774206732	0774206846	0774206960		0778480112	0778480226	0778480340	0778480454	0778480568	0778480682	
	0774206734	0774206848	0774206962		0778480114	0778480228	0778480342	0778480456	0778480570	0778480684	
_	0774206736	0774206850	0774206964		0778480116	0778480230	0778480344	0778480458	0778480572	0778480686	
_	0774206738	0774206852	0774206966		0778480118	0778480232	0778480346	0778480460	0778480574	0778480688	
	0774206740	0774206854	0774206968		0778480120	0778480234	0778480348		0778480576	0778480690	
-	0774206742	0774206856	0774206970		0778480122	0778480236	0778480350	0778480464	0778480578	0778480692	
0774206530	0774206744	0774206858 0774208972	07742069721		0778480124	0778480238	0778480238 0778480352 0778480466 0778480580 0778480694	07784804661	07784805801	O77RARORGA!	











Plan Hillsborough planhillsborough.org planner@plancom.org 813 - 272 - 5940 601 E Kennedy Blvd 18th floor Tampa, FL, 33602

Unincorporated Hillsborough Cou	unty Rezoning Consistency Review
Hearing Date: July 21, 2025	Case Number: PD 25-0744
Report Prepared: July 10, 2025	Folio(s): 77848.0708
	General Location: South of County Road 672, west of Carlton Lake Road, and north of Sweat Loop Road
Comprehensive Plan Finding	CONSISTENT
Adopted Future Land Use	Residential-4 (4 du/ga;0.25 FAR)
Service Area	Urban Service Area
Community Plan(s)	Balm + SouthShore Areawide Systems
Rezoning Request	Major Modification to Rhodine Borrow Pit and the Grove Parcel PD to increase residential entitlements (max of 700 units) and eliminate non-residential entitlements.
Parcel Size	+/- 178 acres
Street Functional Classification	County Road 672 – County Arterial Balm Wimauma Road – County Collector Sweat Loop Road – County Collector Balm Road – County Collector Shelley Lane – Local
Commercial Locational Criteria	Not applicable

Evacuation Area	None

	Table 1: COMPARISON	N OF SURROUNDING PR	ROPERTIES
Vicinity	Future Land Use Designation	Zoning	Existing Land Use
Subject Property	Residential-4	PD	Vacant
North	Residential-4 + Residential Planned-2	PD + ASC-1	Agricultural + HOA/Common Property + Public/Quasi
South	Residential-4	PD	Single-Family + Vacant
East	Residential Planned-2 + Residential-4	AR + PD	Single-Family + Vacant + Heavy Industrial
West	Residential-4 + Residential Planned-2	AS-0.4 + ASC-1 + PD	Single-Family + Agricultural + Vacant + Public/Quasi

Staff Analysis of Goals, Objectives and Policies:

The ± 178 acre subject site is located south of County Road 672, west of Carlton Lake Road, and north of Sweat Loop Road. The site is in the Urban Service Area and is within the limits of the Balm and SouthShore Areawide Systems Community Plans. This rezoning has concurrent Comprehensive Plan Map Amendments to change the Future Land Use to Residential-4 (RES-4) and the Rural Area to the Urban Service Area. Both amendments were approved by the Board of County Commissioners and were effective as of June 22, 2025. Therefore, the subject site now has a Future Land Use (FLU) designation of Residential-4 and will be reviewed as such. The intent of the RES-4 category is for low density residential development. The applicant is requesting a Major Modification to the Rhodine Borrow Pit and the Grove Parcel PD to increase residential entitlements and eliminate non-residential entitlements. The proposed change will exclusively affect the Grove Parcel and the entitlements on the Rhodine Parcel will remain unchanged. The applicant is proposing 700 single family units on the site. See table below for Modifications.

EXISTING PD ENTITLEMENTS	Area (ac)	residential SFD units	non- residential SF	village green SF
Rhodine Parcel	177.3	283	3,820.5	-
The Grove Parcel	178	356	5,000	4,806
Total	358.3	639	8,820.5	-
PROPOSED PD ENTITLEMENTS	Area (ac)	residential SFD units	non- residential SF	village green SF
	Area (ac) 177.3			_
ENTITLEMENTS		units	residential SF	_
ENTITLEMENTS Rhodine Parcel		units	residential SF	_

The site is in the Urban Service Area where, according to Objective 1.1 of the Future Land Use Section (FLUS), 80 percent of the county's growth is to be directed. Policy 3.1.3 requires all new developments to be compatible with the surrounding area, noting that "compatibility does not mean "the same as." Rather, it refers to the sensitivity of development proposals in maintaining the character of existing development." The site currently has vacant land uses. There are single-family, public/quasi-public, agricultural, and vacant land uses surrounding the site. The proposed Major Modification to increase residential entitlements, which will result in 700 additional single-family residential dwelling units, meets the intent of FLUS Objective 1.1

Per Objective 2.2, Future Land Use categories outline the maximum level of intensity or density, and range of permitted land uses allowed in each category. Table 2.2 contains a description of the character and intent permitted in each of the Future Land Use categories. The site is in the Residential-4 (RES-4) Future Land Use category, which allows for the consideration of agricultural, residential, neighborhood commercial, office uses and multi-purpose projects. As the language states above, residential uses are allowed and therefore, the proposal meets Objective 2.2 and the associated policies.

The Comprehensive Plan requires that all development meet or exceed the land development regulations in Hillsborough County (FLUS Objective 4.1, FLUS Policy 4.1.1 and FLUS Policy 4.1.2). However, at the time of uploading this report, Transportation comments were not yet available in Optix and thus were not taken into consideration for analysis of this request.

The proposal meets the intent of FLUS Objective 4.4 and FLUS Policy 4.4.1 that require new development to be compatible to the surrounding neighborhood. In this case, the surrounding land use pattern is comprised mostly of single-family, public/quasi-public, agricultural, and vacant. The proposed request will complement the area as well as the surrounding neighborhoods to the east, north, and west.

The Environmental Protection Commission (EPC) Wetlands Division has reviewed the proposed rezoning. The EPC has determined there are wetlands in southwestern portion of the property. According to Objective 6.2 of the Future Land Use Section, "New development and redevelopment shall not adversely impact environmentally sensitive areas and other significant natural systems as described and required within the Environmental and Sustainability Section and the Coastal Management Section of the Comprehensive Plan." EPC determined that a resubmittal is not necessary; therefore, the proposed Planned Development is consistent with FLUS Objective 6.2.

The subject site is within the limits of the Balm Community Plan and SouthShore Areawide Systems Plan. There are no applicable policies related to this Major Modification request.

Overall, staff finds that the proposed use is an allowable use in the RES-4 category and is compatible with the existing development pattern found within the surrounding area. The proposed Major Modification (MM) would allow for development that is consistent with the Goals, Objectives, and Policies of the *Unincorporated Hillsborough County Comprehensive Plan*.

Recommendation

Based upon the above considerations and the following Goals, Objectives and Policies, Planning Commission staff finds the proposed Major Modification **CONSISTENT** with the *Unincorporated Hillsborough County Comprehensive Plan*, subject to the conditions proposed by the Development Services Department.

Staff Identified Goals, Objectives and Policies of the *Unincorporated Hillsborough County Comprehensive Plan* Related to the Request:

FUTURE LAND USE SECTION

Urban Service Area

Objective 1.1: Direct at least 80% of new population growth into the USA and adopted Urban expansion areas through 2045. Building permit activity and other similar measures will be used to evaluate this objective.

Relationship to the Future Land Use Map

Goal 2: Ensure that the character, compatibility and location of land uses optimize the combined potential for economic benefit, fiscal sustainability, protection of natural resources and maintaining viable agriculture. Ensure density and intensities are maintained through the Future Land Use Map. **Objective 2.1**: The Future Land Use Map is a regulatory tool governing the pattern of development in unincorporated Hillsborough County through the year 2045.

Policy 2.1.1: The Future Land Use Map shall identify Future Land Use categories, summarized in Table 2.2 and further des

Future Land Use Categories

Objective 2.2: The Future Land Use Map (FLUM) Shall identify Land Use Categories, summarized in table 2.2 of the Future Land Use Element.

Policy 2.2.1: The character of each land use category is defined by building type, residential density, functional use, and the physical composition of the land. The integration of these factors sets the general atmosphere and character of each land use category. Each category has a range of potentially permissible uses which are not exhaustive, but are intended to be illustrative of the character of uses permitted within the land use designation. Not all of those potential uses are routinely acceptable anywhere within that land use category.

Compatibility

- **Policy 3.1.1:** Restrict incompatible land uses to protect established and planned neighborhoods and communities by utilizing planning principles that limit commercial development in residential Future Land Use categories. Commercial and mixed-use in residential Future Land Use categories shall be limited to neighborhood serving guided by the commercial locational criteria in Objective 4.7.
- **Policy 3.1.2**: Gradual transitions of intensities and densities between different land uses shall be provided for as new development is proposed and approved through the use of professional site planning, buffering and screening techniques and control of specific land uses. Screening and buffering used to separate new development from the existing, lower-density community should be designed in a style compatible with the community and allow pedestrian penetration. In rural areas, perimeter walls are discouraged and buffering with berms and landscaping are strongly encouraged.
- **Policy 3.1.3:** Any density increase shall be compatible with existing, proposed or planned surrounding development. Compatibility is defined as the characteristics of different uses or activities or design which allow them to be located near or adjacent to each other in harmony. Some elements affecting compatibility include the following: height, scale, mass and bulk of structures, pedestrian or vehicular traffic, circulation, access and parking impacts, landscaping, lighting, noise, odor and architecture. Compatibility does not mean "the same as." Rather, it refers to the sensitivity of development proposals in maintaining the character of existing development

Development

- **Policy 4.1.1**: Each land use plan category shall have a set of zoning districts that may be permitted within that land use plan category, and development shall not be approved for zoning that is inconsistent with the plan.
- **Policy 4.1.2:** Developments must meet or exceed the requirements of all land development regulations as established and adopted by Hillsborough County, the state of Florida and the federal government unless such requirements have been previously waived by those governmental bodies.
- **4.1.6**: Existing and future land development regulations shall be made consistent with the Comprehensive Plan, and all development approvals shall be consistent with those development regulations per the timeframe provided for within Chapter 163, Florida Statutes. Whenever feasible and consistent with Comprehensive Plan policies, land development regulations shall be designed to provide flexible, alternative solutions to problems.

Neighborhood/Community Development

- **Objective 4.4:** Neighborhood Protection Enhance and preserve existing neighborhoods and communities. Design neighborhoods which are related to the predominant character of their surroundings.
- **Policy 4.4.1:** Any density or intensity increases shall be compatible with existing, proposed or planned surrounding development. Development and redevelopment shall be integrated with the adjacent land uses through:
- a) the creation of like uses; and

- b) creation of complementary uses; and
- c) mitigation of adverse impacts; and
- d) transportation/pedestrian connections; and
- e) Gradual transitions of intensity

Environmental Considerations

Objective 6.2: New development and redevelopment shall not adversely impact environmentally sensitive areas and other significant natural systems as described and required within the Environmental and Sustainability Section and the Coastal Management Section of the Comprehensive Plan.

MM 25-0745

HILLSBOROUGH COUNTY

FUTURE LAND USE RZ MM 25-0745

CONTINUED APPROVED DENIED

WITHDRAWN

Tampa Service Area Urban Service Area PENDING Shoreline

AGRICULTURAL/MINING-1/20 (.25 FAR) wam.NATURAL.LULC_Wet_Poly

Jurisdiction Boundary

Major Roads

County Boundary

PEC PLANNED ENVIRONMENTAL COMMUNITY-1/2 (.25 FAR) AGRICULTURAL-1/10 (.25 FAR)

AGRICULTURAL ESTATE-1/2.5 (.25 FAR) AGRICULTURAL/RURAL-1/5 (.25 FAR) RESIDENTIAL-1 (.25 FAR)

RESIDENTIAL PLANNED-2 (.35 FAR) RESIDENTIAL-2 (.25 FAR)

RESIDENTIAL-4 (.25 FAR)

RESIDENTIAL-6 (.25 FAR) RESIDENTIAL-9 (.35 FAR)

RESIDENTIAL-12 (.35 FAR)

RESIDENTIAL-16 (.35 FAR)

RESIDENTIAL-20 (.35 FAR) RESIDENTIAL-35 (1.0 FAR)

NEIGHBORHOOD MIXED USE-4 (3) (.35 FAR) SUBURBAN MIXED USE-6 (.35 FAR)

COMMUNITY MIXED USE-12 (.50 FAR) URBAN MIXED USE-20 (1.0 FAR)

INNOVATION CORRIDOR MIXED USE-35 (2.0 FAR) REGIONAL MIXED USE-35 (2.0 FAR)

RESEARCH CORPORATE PARK (1.0 FAR) OFFICE COMMERCIAL-20 (.75 FAR)

ENERGY INDUSTRIAL PARK (.50 FAR USES OTHER THAN RETAIL, .25 FAR RETAIL/COMMERCE)

LIGHT INDUSTRIAL PLANNED (.75 FAR) LIGHT INDUSTRIAL (.75 FAR)

WIMAUMA VILLAGE RESIDENTIAL-2 (.25 FAR) NATURAL PRESERVATION PUBLIC/QUASI-PUBLIC

HEAVY INDUSTRIAL (.75 FAR)

CITRUS PARK VILLAGE



2,200

1,100

Map Printed from Rezoning System: 5/28/2025

Author: Beverly F. Daniels

